



Arboricultural Assessment Report
Gunnersbury Park, Ealing

Chris Alder MSc HNDArb FArborA MICFor

9 October 2015
15323-AA2-CA

Report purpose, validation statement and tree protection plan

Report purpose

This is a BS 5837 compliant arboricultural assessment report providing sufficient information for the Local Planning Authority ("LPA") to consider the effect of the proposed development on local character from a tree perspective. It includes an analysis of how trees will be affected and a heads of terms arboricultural method statement briefly describing how retained trees will be protected and managed during the development activity.

Validation statement

For LPA validation purposes, this report includes:

- a **BS 5837 compliant tree survey**, including a tree protection plan showing the location of the existing trees, their categorisation, the location of the new structures and hard surfacing, the trees to be removed and the tree protection measures;
- an **arboricultural assessment** in Section 1, which describes how the development proposal will affect local character from a tree perspective;
- an **arboricultural method statement** (heads of terms only as recommended in BS 5837) in Section 2, which summarises the tree protection measures; and
- several **appendices** in Section 3 setting out the background administrative information and a schedule of tree information.

The tree protection plan

More specifically, the tree protection plan is based on the provided information and it should only be used for dealing with the tree issues. It shows:

- the existing trees numbered, with high/moderate categories (A & B) highlighted in green triangles and low/unsuitable categories (C & U) highlighted in blue rectangles;
- the circular interpretation of root protection areas ("RPA") of category A, B and C trees (grey circles);
- the trees to be removed indicated by a red number and crown outline;
- the location of the construction exclusion zone ("CEZ"), which is the area of restricted access, to be protected by temporary barriers (fencing and/or ground protection); and
- the location of precautionary areas outside the CEZ where limited, but careful access is permitted.

Summary

1. The development proposal

The development proposal is to construct new sports facilities and associated infrastructure at Gunnersbury Park, Ealing.

2. Background administrative information

Our instructions, how we prepared this report and other relevant background information is explained in Appendix 1. All the trees that could be affected were inspected and that information is listed in Appendix 2.

3. Table 1: Summary of category A, B and C trees to be removed, pruned or protected using special precautions

	British Standard 5837 Category		
	A (High quality)	B (Moderate quality)	C (Low quality)
Remove			33, H47(part), 49, 50, H55(part), G56, G57, G58, G124, G125, G126
Protect using special precautions	24, 42, 44, 45, 46, 103, 115	31, 34, 35, 43, 53, 102, 104, 107, 109, 110	32, 36

H = Hedge; G = Group

Note: Category U trees are in such poor condition they would be removed irrespective of development and they are not included in this summary.

4. Table 2: Summary of the impact on local character of tree removal and pruning, and proposed mitigation

	Tree number(s)	Impact on local character	Mitigation
Remove	33, H47(part), 49, 50, H55(part), G56, G57, G58, G124, G125, G126	No impact: Whilst not prominent as individual features, their removal will be noticeable in the immediate vicinity in the short term, but there will be no significant visual impact in the wider setting beyond the short term.	New landscape planting to encompass all mitigation

5. Protection of retained trees

As recommended in BS 5837 (Table B1), a heads of terms arboricultural method statement is included in Section 2 of this report. The approximate location of the protective measures are shown on the tree protection plan.

6. Enhancement through new tree planting

In order to increase the contribution of trees to local character, a new landscape strategy is feasible to provide sustainable planting across the site. The new trees would have the potential to reach a significant height without excessive inconvenience, representing an overall enhancement of tree cover in the area.

Summary

7. Overall assessment of how the development proposal will affect local character from a tree perspective

The trees to be lost because of this proposal are low category because of their poor condition or small size. All the significant boundary tree cover will remain intact and no moderate or high category trees will need to be removed. There is plenty of space for tree planting and a comprehensive new tree planting scheme is feasible. The construction activity and proposed changes may affect further trees if appropriate protective measures are not taken. However, if adequate precautions to protect the retained trees are specified and implemented through the arboricultural method statement included in this report, the overall impact of the proposal on local character will be limited to the short term only.

Section 1

Arboricultural assessment

This arboricultural assessment has taken account of all the recommendations set out in 5.4 of BS 5837 (reproduced courtesy of BSI below).

5.4 Arboricultural impact assessment

5.4.1 The project arboriculturist should use the information detailed in 5.2 and 5.3 to prepare an arboricultural impact assessment that evaluates the direct and indirect effects of the proposed design and where necessary recommends mitigation.

5.4.2 The assessment should take account of the effects of any tree loss required to implement the design, and any potentially damaging activities proposed in the vicinity of retained trees. Such activities might include the removal of existing structures and hard surfacing, the installation of new hard surfacing, the installation of services, and the location and dimensions of all proposed excavations or changes in ground level, including any that might arise from the implementation of the recommended mitigation measures. In addition to the impact of the permanent works, account should be taken of the buildability of the scheme in terms of access, adequate working space and provision for the storage of materials, including topsoil.

NOTE Scaled cross-sections and other drawings might be required to demonstrate the feasibility of the proposals (see Annex B).

5.4.3 As well as an evaluation of the extent of the impact on existing trees, the arboricultural impact assessment should include:

- a) the tree survey (see 4.4);
- b) trees selected for retention, clearly identified (e.g. by number) and marked on a plan with a continuous outline;
- c) trees to be removed, also clearly identified (e.g. by number) and marked on a plan with a dashed outline or similar;
- d) trees to be pruned, including any access facilitation pruning, also clearly identified and labelled or listed as appropriate;
- e) areas designated for structural landscaping that need to be protected from construction operations in order to prevent the soil structure being damaged;
- f) evaluation of impact of proposed tree losses;
- g) evaluation of tree constraints (see 5.2) and draft tree protection plan (see 5.5);
- h) issues to be addressed by an arboricultural method statement (see 6.1), where necessary in conjunction with input from other specialists.

Section 1: Arboricultural assessment

8. Relevant strategic and policy considerations

The Climate Change Act (2008) sets out a statutory strategic need to adapt to climate change at a national and local level, which is reiterated through the emphasis on sustainability in the National Planning Policy Framework. It is now widely accepted that trees offer significant climate adaptation benefits to the built environment where people live and work. These benefits include, amongst others, the buffering of temperature extremes and the buffering of rainwater runoff, which can significantly reduce the adverse impacts of climate change.

Additionally, there is an increasing body of research providing reliable evidence that trees impart other significant health-related benefits to the people that live and work near them. These benefits include, amongst others, the potential to improve psychological wellbeing by reducing stress and anxiety through the relaxing nature of their presence. It seems that access to greenspace and trees makes people happier and encourages them to take more exercise, which has a direct and positive impact on physical health and wellbeing. On a subtler level, the ecological enhancement that can be achieved through appropriate tree management makes a positive contribution to environmental sustainability.

These concepts are explored and set into a built-environment context in the recent Trees and Design Action Group's publications *Trees in the Townscape: A Guide for Decision Makers* and *Trees in Hard Landscapes: A Guide for Delivery*. Furthermore, specific advice on planting new trees is provided in British Standard 8545 (2014) *Trees: from nursery to independence in the landscape – Recommendations*. We have given significant weight to the guidance set out in these documents, which is reflected in the analyses in this report.

In line with these references, we agree with and support the general principle that more and bigger trees will deliver more benefits from their presence. Although this must be applied with balance and intelligence, it nonetheless remains an important guiding principle in the planning process and it has been an influential consideration in our analysis on this site.

9. Table 3: The impact of tree removal on local character

	Impact of tree removal
Category A	<ul style="list-style-type: none"> No category A trees will be removed
Category B	<ul style="list-style-type: none"> No category B trees will be removed
Category C (33, H47(part), 49, 50, H55(part), G56, G57, G58, G124, G125, G126)	<ul style="list-style-type: none"> No impact: Whilst not prominent as individual features, their removal will be noticeable in the immediate vicinity in the short term, but there will be no significant visual impact in the wider setting beyond the short term. The trees are mainly small and insignificant in wider landscape terms and make very little contribution to the overall character of the area.
Category U (38, 39, 41, 51, 52, 73, 75, 129, 133)	Trees categorised as U are in such poor condition that they have been assessed as needing removal for management reasons irrespective of any development proposals. Removal of any category U trees will be a management decision and their loss will not be caused by this proposal and it should not be considered as a direct impact.

Section 1: Arboricultural assessment

10. Table 5: Trees that need special precautions to be successfully retained

	Special precautions
Category A (24, 42, 44, 45, 46, 103, 115)	<ul style="list-style-type: none"> Existing surfacing within RPAs may be replaced with new surfacing and landscaping. No excavation will be undertaken into existing soil beneath the sub-base. New surfacing will be permeable where possible. Ground protection will be installed over any exposed soil within RPAs outside the barriers for the duration of activity.
Category B (31, 34, 35, 43, 53, 102, 104, 107, 109, 110)	<ul style="list-style-type: none"> Existing surfacing within RPAs may be replaced with new surfacing and landscaping. No excavation will be undertaken into existing soil beneath the sub-base. New surfacing will be permeable where possible. Ground protection will be installed over any exposed soil within RPAs outside the barriers for the duration of activity.
Category C (32, 36)	<ul style="list-style-type: none"> Category C trees are not sufficiently important to warrant any special precautions to ensure their retention. However, where appropriate, they can be retained within the wider tree protection provisions for the site and are shown for retention.

RPA = Root Protection Area

These development activities may cause harm if not carried out with care. We have reviewed the situation carefully and our experience is that these trees could be successfully retained without any significant adverse impact if appropriate protective measures are properly specified and controlled through an arboricultural method statement.

11. New tree planting to mitigate tree removals

To mitigate the loss of trees, a tree planting scheme is feasible as part of the wider landscape strategy for the site, which could include new trees to be planted around the site in sustainable locations. The final selection of species, size and location are flexible and open to amendment if necessary. The new trees would have the potential to reach a significant height without excessive inconvenience and be sustainable into the long term, significantly improving the potential of the site to contribute to local character.

12. Summary of the impact on local character

The trees to be lost because of this proposal are low category because of their poor condition or small size. All the significant boundary tree cover will remain intact and no moderate or high category trees will need to be removed. There is plenty of space for tree planting and a comprehensive new tree planting scheme is feasible. The construction activity and proposed changes may affect further trees if appropriate protective measures are not taken. However, if adequate precautions to protect the retained trees are specified and implemented through the arboricultural method statement included in this report, the overall impact of the proposal on local character will be limited to the short term only.

Section 2

Arboricultural method statement (heads of terms)

As recommended in Table B1 of BS 5837 (reproduced courtesy of BSI below), this arboricultural method statement is confined to a summary of the heads of terms, with the detail to be provided at the reserved matters stage in response to a planning condition.

Stage of process	Minimum detail	Additional information
Pre-application	Tree survey	Tree retention/removal plan (draft)
Planning application	<p>Tree survey (in the absence of pre-application discussions)</p> <p>Tree retention/removal plan (finalized)</p> <p>Retained trees and RPAs shown on proposed layout</p> <p>Strategic hard and soft landscape design, including species and location of new tree planting</p> <p>Arboricultural impact assessment</p>	<p>Existing and proposed finished levels</p> <p>Tree protection plan</p> <p>Arboricultural method statement – heads of terms</p> <p>Details for all special engineering within the RPA and other relevant construction details</p>
Reserved matters/ planning conditions	<p>Alignment of utility apparatus (including drainage), where outside the RPA or where installed using a trenchless method</p> <p>Dimensioned tree protection plan</p> <p>Arboricultural method statement – detailed</p> <p>Schedule of works to retained trees, e.g. access facilitation pruning</p> <p>Detailed hard and soft landscape design</p>	<p>Arboricultural site monitoring schedule</p> <p>Tree and landscape management plan</p> <p>Post-construction remedial works</p> <p>Landscape maintenance schedule</p>

Section 2: Arboricultural method statement (heads of terms)

13. Table 6: Heads of terms arboricultural method statement

Heads of terms	Overview of appropriate protective measures (to be detailed in response to a planning condition once consent has been given)
Identification of areas to be protected	The tree protection plan shows all the areas where protective measures are necessary. The construction exclusion zone ("CEZ") boundary is shown on the plan as the heavy dashed black line, with the lighter diagonal hatching behind. If necessary, further precautionary areas outside the CEZ are shown on the plan as a yellow coloured fill, where a high level of care is required. This work will be subject to arboricultural supervision.
Tree works	Tree works, based on our assessment of the proposal and the original site inspection, are set out in the work recommendations column of the tree schedule in Appendix 2. The location of each tree by number is shown on the tree protection plan and any to be removed are indicated with a red crown outline. All tree works must be reassessed before any site activity starts as part of the standard risk management process.
Fencing	Protective fencing must be installed at the locations shown on the tree protection plan by the heavy black dashed line. If agreed with the LPA, fencing can be set back to improve access, provided the exposed ground is protected with ground protection. This work will be subject to arboricultural supervision.
Ground protection	Ground protection must be installed wherever RPAs are exposed and not enclosed by fencing. This will be where fencing has been agreed to be set back, and in all precautionary areas. This work will be subject to arboricultural supervision.
Existing surfacing to be retained	The existing hard surfacing will be retained and utilised where possible. Any surfacing disrupted during the course of the construction activity will be reconditioned or upgraded as necessary. This work will be subject to arboricultural supervision.
Installation of new surfacing	New surfacing within RPAs is proposed as shown on the tree protection plan. These will be installed in accordance with the appropriate guidance. This work will be subject to arboricultural supervision.
New and existing services	All excavation for the installation of new services or the upgrading of existing services must be carried out in accordance with the appropriate guidance. This work will be subject to arboricultural supervision.
Removal of protection	All protective barriers must remain in place until the construction activity is finished and there is no realistic risk of damage to the protected soil surfaces. This work will be subject to arboricultural supervision.
Tree planting	Space has been allowed for a comprehensive new tree planting scheme. It would be appropriate for the precise detail to be agreed with the LPA through a planning condition.
Landscaping	All landscaping activity must be carefully controlled once the protective measures have been removed. This work will be subject to arboricultural supervision.
Other risks to trees	Any significant risk to trees from activities outside RPAs, but close enough to have a knock-on impact, must be assessed and appropriate precautions put in place to reduce that risk. Such risks include, <i>inter alia</i> , chemical pollution, cranes and high loads.

14. Heads of terms construction method statement

A construction method statement is a description of how operations that may affect trees will be carried out to minimise any adverse impact on them. The details of how the site will be managed are construction and contractual matters that can only be finalised once the post-consent detailed planning begins. For that reason, at this stage in the planning process, it is only possible to list a heads of terms summary of the issues that will require more detailed consideration once consent is issued. The issues that are likely to require further explanation on this site include:

1. The order of work on site, including demolition, site clearance and building work.
2. Erection and maintenance of security hoarding near trees.

Section 2: Arboricultural method statement (heads of terms)

3. Who will be responsible for protecting the trees on site.
4. Detailed proposals for inspecting and supervising the tree protection, and how problems will be reported and solved.
5. How accidents and emergencies involving trees will be managed, including accidental damage to roots and their treatment.
6. Details of facilitation pruning and access into site. What size vehicles will be used under canopies and will large machinery be lifted over trees.
7. The parking arrangements for workers and visitors.
8. A schedule of emergency contact numbers.
9. Areas for loading and unloading of materials and storage of materials and plant.
10. Where site facilities will be sited and when will they be installed.
11. Crane location and zones of movement.
12. How machinery and equipment (such as excavators, cranes and their loads, concrete pumps and piling rigs) will enter, move on, work on and leave the site.
13. Wheel washing facilities near trees.
14. Measures to control the emission of dust and dirt during construction near trees.
15. Recycling and storage of waste near trees.
16. Details of earthworks, grading and mounding and removal of spoil, including any planned lowering or raising of ground levels.
17. Details of upgrading/removing/replacing existing surfacing and areas where this will happen, including detailed and precise cross-sections where no-dig surfacing is to be installed.
18. How and when any temporary surfacing will be laid and removed.
19. Details of piling operations.
20. Precise services locations, including the method of excavation when near trees.
21. Proposed locations of site facilities/crane location/material storage/loading bays etc.
22. Finished excavation lines for basement works.
23. How post-construction damage through compaction to soil near existing trees and new trees will be ameliorated.

Note: It is not our role as arboricultural consultants to detail the timing and implementation of these measures, although we can input into the process and will need to confirm that the final proposals will not adversely affect retained trees.

15. Arboricultural supervision

An arboricultural consultant must be appointed by the developer to advise on the tree management for the site and to attend:

1. a pre-commencement meeting before any work starts;
2. regular supervision visits to oversee the agreed tree protection; and
3. further supervision visits as necessary to oversee any unexpected works that could affect trees.

Section 3

Appendices

Appendix 1: Background administrative information, data collection and any additional relevant information

16. Table 7: Background administrative information

	Background administrative information
Report date & reference	09/10/2015 – 15323-AA2-CA
Tree protection plan reference	BT2
Our instructing client	London Borough of Ealing Council
Our instructions	Visit the site, assess the relevant trees, prepare a schedule of their details, describe the impact of the proposal on those trees and identify the tree protection issues in an arboricultural method statement confined to the heads of terms
Provided documents	Land survey, drawing number Gunnersbury WD Survey Master Nov14 V2004.dwg received by email on 1 September 2015 and layout, drawing number 3399-ASP-ST4-XX-M3-A-MODEL_15_viota-giannini@s-architects – Floor Plan -... .dwg received by email on 7 October 2015
Report author and credentials	Chris Allder is a Chartered Forester (www.charteredforesters.org) and fully qualified to undertake the assessments in this report. Further details of his credentials can be found at www.barrelltreecare.co.uk/career-summaries/Chris
Report limitations	We have not checked if the trees are protected. If any tree works are proposed before a planning consent is given, then the existence of any statutory protection must be checked with the LPA. This report does not consider ecological or archaeological issues, or any other matter beyond the assessment of the trees.
Technical references	<p>In preparing the analysis in this report, detailed consideration was given to the guidance and advice in the following technical references:</p> <ul style="list-style-type: none"> • Climate Change Act (2008) www.legislation.gov.uk/ukpga/2008/27/contents • Town and Country Planning Act 1990 http://www.legislation.gov.uk/ukpga/1990/8/contents • National Planning Policy Framework (“NPPF”), published by the DCLG www.gov.uk/government/publications/national-planning-policy-framework--2 • BS 5837 (2012) <i>Trees in relation to design, demolition and construction – Recommendations</i>, BSI www.shop.bsigroup.com/en/ProductDetail/?pid=00000000030213642 • BS 8545 (2014) <i>Trees: from nursery to independence in the landscape – Recommendations</i>, BSI www.shop.bsigroup.com/ProductDetail/?pid=00000000030219672 • BS 3998 (2010) <i>Tree work – Recommendations</i>, BSI http://shop.bsigroup.com/ProductDetail/?pid=00000000030089960 • <i>Trees in the Townscape: A Guide for Decision Makers</i>, published by the Trees & Design Action Group www.tdag.org.uk/downloads.html • <i>Trees in Hard Landscapes: A Guide for Delivery</i>, published by the Trees & Design Action Group www.tdag.org.uk/downloads.html • National Joint Utilities Group (2007) Volume 4, Issue 2: <i>Guidelines for the planning, installation and maintenance of utility apparatus in proximity to trees</i> www.njug.org.uk/publications/

Appendix 1: Background administrative information, data collection and any additional relevant information

17. Table 8: Data collection

	Data collection
Date of site visit	08/09/2015 & 11/09/2015
People present during site visit	Chris Allder
Weather & visibility	Clear, still and dry, with good visibility
Limitations to observations	<ul style="list-style-type: none"> • Our inspection of the trees for the purposes of assessing their condition and work requirements is made on the basis that they will be annually inspected in the future to identify any changes in condition and review the original recommendations. For these reasons, the tree assessment advice only remains valid for one year from the date that the trees were last inspected. • All observations were of a preliminary nature and did not involve any climbing or detailed investigation beyond what was visible from accessible points at ground level. • Observations of trees outside the site boundaries are confined to what was visible from within the site. • All dimensions were estimated unless otherwise indicated.
Tree location and numbering	Each tree was inspected and the numbering scheme is indicated on the tree protection plan. If appropriate, obvious hedges and groups were identified and numbered. If important trees were found on site that were not included on the provided plan, their approximate positions and canopy extents are indicated on the plan.
Recording of tree data	For each tree and any group or hedge found on site, the information collected was recorded on the tree schedule in Appendix 2 and the tree protection plan.
Compliance of data collection with BS 5837	The data collection is fully compliant with the advice in subsection 4.4.2 of BS 5837. When collecting this information, specific consideration was given to any low branches that may influence future use, age class, physiological condition, structural condition and remaining contribution. Where appropriate, crown spreads were also noted where they differed from those shown on the provided land survey.
Calculation of RPAs	Following the recommendations in Table D1 of BS 5837, the diameter of each tree was rounded up to the next 2.5cm increment, with the radius of a nominal circle and the resultant RPA taken directly from that table. This information is listed for each tree in the tree schedule in Appendix 2.

Appendix 2: Tree schedule and explanatory notes

NOTE: Colour annotation is **A & B trees with green background;** **C & U trees with blue background;** **trees to be removed in red text.**

Tree No	Species	Height (m)	Diameter (cm) @ 1.5m	Maturity	Low Branches	Category	Notes	Tree Works	RPA radius (m)	RPA area (m ²)
All retained trees & hedges								Carry out safety check and lift over site to 3-4m as necessary.		
T1	Lime	16	60*	Mature	-	A	TAG 1532 dense canopy, minor deadwood	-	7.2	163
T2	Lime	4	15	Young	-	C	New planting, on stake	-	1.8	10
T3	Ash	5	15	Young	-	C	New planting, on stake	-	1.8	10
T4	Lime	15	55	Mature	-	A	Dense crown, history of minor Pruning	-	6.6	137
T5	False acacia	13	70	Mature	-	C	TAG 1536 dieback, stem defects and decay, buttress defects, poor	-	8.4	222
T6	Norway maple	18	67.5*	Mature	-	A	TAG 1537 high crown, crown lift	-	8.1	206
T7	Norway maple	16	45*	Mature	-	B	TAG 1538 minor stem defect and wound	-	5.4	92
T8	Norway maple, ash	20	85*	Mature	-	B	TAG 1539 previously reduced, deadwood and dense	-	10.2	327
T9	Sycamore	15	52.5*	Mature	-	B	TAG 1540 sparse crown, slight lean	-	6.3	125
T10	Horse chestnut	18	80*	Mature	-	B	TAG 1541 stem defects, bark loss, dense crown	-	9.6	290
T11	Norway maple	15	37.5*	Mature	-	C	TAG 1542 suppressed	-	4.5	64
T12	Sycamore	18	55*	Mature	-	B	Thin crown	-	6.6	137
T13	Lime	4	15	Young	-	C	New planting	-	1.8	10
T14	Horse chestnut	18	87.5*	Mature	-	B	Leaning bark exudation, early browning	-	10.5	346
T15	Ash	5	15	Young	-	C	New planting	-	1.8	10

Appendix 2: Tree schedule and explanatory notes

Tree No	Species	Height (m)	Diameter (cm) @ 1.5m	Maturity	Low Branches	Category	Notes	Tree Works	RPA radius (m)	RPA area (m ²)
T16	Horse chestnut	18	82.5*	Mature	-	B	TAG 1546, early browning	-	9.9	308
T17	False acacia	5	45*	Young	-	C	Multi stemmed regrowth out of old stump	-	5.4	92
T18	Lime	4	15	Young	-	C	New planting	-	1.8	10
T19	Ash	20	80	Mature	-	A	TAG 1548 minor deadwood	-	9.6	290
T20	Elm	14	60*	Mature	-	C	Twin stemmed at 1m, leaning, dieback	-	7.2	163
T21	Oak	15	37.5*	Mature	-	B	Minor deadwood, one-sided	-	4.5	64
T22	Oak	18	55*	Mature	-	A	-	-	6.6	137
T23	Horse chestnut	12	45*	Mature	-	C	Stem defects, poor	-	5.4	92
T24	London plane	20	75*	Mature	-	A	Previously reduced	-	9.0	254
T25	Ash	20	80	Mature	-	C	Reduced, significant cavity in main stem	-	9.6	290
T26	London plane	10	30*	Maturing	-	B	-	-	3.6	41
T27	London plane	10	35*	Maturing	-	B	-	-	4.2	55
T28	London plane	10	37.5*	Maturing	-	B	-	-	4.5	64
T29	Red oak	10	30	Maturing	-	B	-	-	3.6	41
T30	London plane	5	20	Maturing	-	C	Previously topped	-	2.4	18
T31	Poplar	25	127.5*	Mature	-	B	Previously reduced	-	15.0	707
T32	Oak	6	20	Maturing	-	C	Poor	-	2.4	18
T33	Poplar	14	90	Maturing	-	C	Multi stemmed, deformed by concrete slab	Fell	10.8	366
T34	Beech	15	55*	Mature	-	B	One-sided due to poplar	-	6.6	137
T35	Poplar	25	110*	Mature	-	B	Previously reduced	-	13.2	547
T36	Poplar	15	75*	Mature	-	C	Previously reduced	-	9.0	254
T37	Poplar	20	75*	Mature	-	C	Bark failure, sparse canopy, compacted roots	-	9.0	254
T38	Poplar	20	70*	Mature	-	U	Honey fungus at base, sparse crown, root compaction	Fell for management	8.4	222
T39	Poplar	18	70*	Mature	-	U	Leaning, deadwood, dieback	Fell for management	8.4	222

Appendix 2: Tree schedule and explanatory notes

Tree No	Species	Height (m)	Diameter (cm) @ 1.5m	Maturity	Low Branches	Category	Notes	Tree Works	RPA radius (m)	RPA area (m ²)
T40	London plane	8	32*	Maturing	-	B	Suppressed by T39, potential	-	3.8	46
T41	Ash	20	65*	Mature	-	U	Significant dieback, overhanging parking area	Fell for management	7.8	191
T42	London plane	20	90*	Mature	-	A	Compacted ground causing girdling surface roots	-	10.8	366
T43	Horse chestnut	20	110*	Mature	-	B	Minor stem wounds from previous pruning, dense canopy	-	13.2	547
T44	London plane	25	132.5*	Mature	-	A	Multi stemmed at 6m	-	15.0	707
T45	London plane	25	107.5*	Mature	-	A	Slight lean	-	12.9	523
T46	London plane	20	97.5*	Mature	-	A	Slight lean	-	11.7	430
H47	Privet	1.5	15	Maturing	-	C	Clipped hedge	Fell part	1.8	10
G48	Yew, fir	4	20	Maturing	-	C	Small trees	-	2.4	18
T49	Blue spruce	4	20	Maturing	-	C	Small, one-sided	Fell	2.4	18
T50	Horse chestnut	3	15	Young	-	C	Small tree	Fell	1.8	10
T51	Copper beech	16	65*	Mature	-	U	TAG 1632 significant basal cavity and decay, stem exudation	Fell for management	7.8	191
T52	Beech	14	95*	Mature	-	U	Meripilus infection at base, previously reduced, overhanging children's play area	Fell for management	11.4	408
T53	Lime	16	77.5*	Mature	-	B	Very dense crown	-	9.3	272
T54	Copper beech	10	42.5*	Mature	-	B	One-sided	-	5.1	82
H55	Leyland cypress	12	30	Mature	-	C	Clipped hedge	Fell part	3.6	41
G56	Oak, ash, laurel	8	30	Maturing	-	C	Dense, linear group	Fell	3.6	41
G57	Cherry, elder	6	30	Maturing	-	C	Dense, small trees	Fell	3.6	41
G58	Birch, field maple	4	15	Young	-	C	Nursery remnants	Fell	1.8	10
G59	Birch	3	15	Young	-	C	New planting	-	1.8	10
T60	Turkey oak	20	75	Mature	-	A	Within play area boundary	-	9.0	254

Appendix 2: Tree schedule and explanatory notes

Tree No	Species	Height (m)	Diameter (cm) @ 1.5m	Maturity	Low Branches	Category	Notes	Tree Works	RPA radius (m)	RPA area (m ²)
T61	Turkey oak	20	70	Mature	-	A	Within play area boundary	-	8.4	222
T62	Beech	10	52.5*	Mature	-	B	-	-	6.3	125
T63	Lime	20	87.5*	Mature	-	B	Twin stemmed at 3m, dense	-	10.5	346
T64	Beech	12	40*	Mature	-	B	Suppressed by T65	-	4.8	72
T65	Oak	20	82.5*	Mature	-	A	Minor deadwood	-	9.9	308
T66	Lime	20	87.5	Mature	-	A	-	-	10.5	346
T67	Copper beech	18	57.5*	Mature	-	B	Minor dieback at tip	-	6.9	150
T68	Beech	5	20	Young	-	C	Small, new planting	-	2.4	18
T69	Copper beech	18	65	Mature	-	A	-	-	7.8	191
T70	Copper beech	18	70*	Mature	-	B	Twin stemmed, tight fork at 3m	-	8.4	222
T71	Copper beech	18	70*	Mature	-	A	-	-	8.4	222
T72	Copper beech	18	60*	Mature	-	A	-	-	7.2	163
T73	Horse chestnut	20	107.5*	Mature	-	U	Significant cavity at base and decay on stem,	Fell for management	12.9	523
T74	Oak	25	100*	Mature	-	A	-	-	12.0	452
T75	Beech	20	70	Mature	-	U	Meripilus infection and decay	Fell for management	8.4	222
T76	Oak	25	95*	Mature	-	A	-	-	11.4	408
T77	Lime	20	60	Mature	-	B	Suppressed by T76	-	7.2	163
T78	Lime	20	82.5*	Mature	-	A	-	-	9.9	308
T79	Oak	18	65*	Mature	-	A	-	-	7.8	191
T80	Sweet chestnut	5	15	Young	-	C	Small new tree	-	1.8	10
T81	Sweet chestnut	4	10	Young	-	C	Small new tree	-	1.2	5
T82	Oak	18	40	Maturing	-	B	Slender, small crown	-	4.8	72
T83	Oak	18	50	Mature	-	B	-	-	6.0	113
T84	Oak	16	45	Maturing	-	B	-	-	5.4	92
T85	Oak	18	60*	Mature	-	A	Edge of group	-	7.2	163
T86	Oak	16	52.5*	Mature	-	B	Minor dieback, one-sided	-	6.3	125
T87	Sycamore	20	70	Mature	-	B	Minor cavity at base	-	8.4	222

Appendix 2: Tree schedule and explanatory notes

Tree No	Species	Height (m)	Diameter (cm) @ 1.5m	Maturity	Low Branches	Category	Notes	Tree Works	RPA radius (m)	RPA area (m ²)
T88	Lime	20	85*	Mature	-	B	Multi stemmed at 4m, dieback and deadwood	-	10.2	327
T89	Lime	25	87.5*	Mature	-	A	-	-	10.5	346
T90	Lime	25	95*	Mature	-	A	-	-	11.4	408
T91	Lime	25	97.5	Mature	-	A	Twin stemmed at 2m	-	11.7	430
T92	Lime	25	100*	Mature	-	B	Twin stemmed at 2m, cavity and included bark in stem	-	12.0	452
T93	Lime	25	92.5*	Mature	-	A	-	-	11.1	387
T94	Lime	25	95*	Mature	-	A	-	-	11.4	408
T95	Lime	25	92.5*	Mature	-	A	Multi stemmed at 4m	-	11.1	387
T96	Lime	25	85*	Mature	-	B	Ganorderma bracket at base, leaning	-	10.2	327
T97	Lime	25	110*	Mature	-	A	Large, open crown	-	13.2	547
T98	Sycamore	15	70*	Mature	-	B	Minor deadwood	-	8.4	222
T99	Oak	3	15	Young	-	C	New planting	-	1.8	10
T100	False acacia	20	70*	Mature	-	C	Stump at base, leaning over car park, fibre buckling	-	8.4	222
T101	Norway maple	15	47.5*	Mature	-	B	Multi stemmed at 3m	-	5.7	102
T102	Tree of heaven	22	82.5*	Mature	-	B	Scar on stem at 3m	-	9.9	308
T103	Maple	18	117.5*	Mature	-	A	Leaning, on mound, minor deadwood	-	14.1	625
T104	Norway maple	14	50*	Maturing	-	B	One sided	-	6.0	113
T105	Tree of heaven	10	35*	Maturing	-	C	Twin stemmed from base, poor	-	4.2	55
T106	Horse chestnut	10	50	Mature	-	C	Twin stemmed at 4m, minor deadwood	-	6.0	113
T107	Ash	18	60	Mature	-	B	Minor deadwood and failed branches	-	7.2	163
T108	Tree of heaven	8	30	Maturing	-	C	Small	-	3.6	41
T109	London plane	20	130	Mature	-	B	Previously reduced, minor deadwood	-	15.0	707

Appendix 2: Tree schedule and explanatory notes

Tree No	Species	Height (m)	Diameter (cm) @ 1.5m	Maturity	Low Branches	Category	Notes	Tree Works	RPA radius (m)	RPA area (m ²)
T110	Norway maple	20	70*	Mature	-	B	Multi stemmed at 4m	-	8.4	222
T111	Ash	20	70	Mature	-	B	Minor deadwood	-	8.4	222
T112	Ash	20	45	Mature	-	C	One sided, deadwood	-	5.4	92
T113	Ash	22	85	Mature	-	B	Multi stemmed at 5m, decay in wound, deadwood	-	10.2	327
G114	Ash, Norway maple, oak	14	40	Maturing	-	B	Small, potential	-	4.8	72
T115	Lime	25	80	Mature	-	A	-	-	9.6	290
T116	Turkey oak	20	75	Mature	-	B	One sided, leaning and suppressed	-	9.0	254
T117	Lime	20	70	Mature	-	B	Previously topped	-	8.4	222
T118	Horse chestnut	18	65	Mature	-	B	Exudate on stem	-	7.8	191
T119	Norway maple	16	60	Mature	-	B	One sided	-	7.2	163
T120	Norway maple	18	65	Mature	-	B	Previously topped	-	7.8	191
T121	Horse chestnut	12	60	Mature	-	C	Poor, full of defects, in decline	-	7.2	163
T122	Lime	18	60	Mature	-	B	Twin stemmed at 4m	-	7.2	163
T123	Horse chestnut	16	75	Mature	-	B	Early browning	-	9.0	254
G124	Tree of heaven	4	20	Young	-	C	Multi stemmed dense group of small trees	Fell	2.4	18
G125	Tree of heaven	6	20	Maturing	-	C	Multi stemmed, dense self seeded	Fell	2.4	18
G126	Leyland cypress	6	40	Maturing	-	C	Overgrown hedge	Fell	4.8	72
G127	Holly, yew	10	45	Maturing	-	C	Dense group, leaning, multi stemmed	-	5.4	92
T128	Cedar of Lebanon	22	127.5	Mature	-	A	Minor defect at base, twin stemmed at 8m	-	15.0	707
T129	Golden false acacia	12	60	Mature	-	U	Decay scar up stem to 3m	Fell for management	7.2	163
T130	Atlantic cedar	14	60	Maturing	-	A	-	-	7.2	163
T131	Sweetgum	8	25	Maturing	-	A	-	-	3.0	28
T132	False acacia	6	20	Maturing	-	B	-	-	2.4	18

Appendix 2: Tree schedule and explanatory notes

Tree No	Species	Height (m)	Diameter (cm) @ 1.5m	Maturity	Low Branches	Category	Notes	Tree Works	RPA radius (m)	RPA area (m ²)
T133	Golden false acacia	10	45	Mature	-	U	In decline, decay and dieback	Fell for management	5.4	92
G134	Yew	8	45	Mature	-	B	Dense, multi stemmed screen	-	5.4	92
T135	Blue spruce	10	40	Maturing	-	B	-	-	4.8	72

Appendix 2: Tree schedule and explanatory notes

Explanatory Notes

- **Abbreviations:**

G : Group
H : Hedge
RPA : Root protection area

- **Botanical tree names:**

Ash	: <i>Fraxinus excelsior</i>
Beech	: <i>Fagus sylvatica</i>
Birch	: <i>Betula pendula</i>
Blue Atlantic cedar	: <i>Cedrus libani atlantica</i> Glauca Group
Blue spruce	: <i>Picea pungens 'Glauca'</i>
Cherry	: <i>Prunus</i> sp
Copper beech	: <i>Fagus sylvatica purpurea</i>
Elder	: <i>Sambucus nigra</i>
Elm	: <i>Ulmus</i> sp
False acacia	: <i>Robinia pseudoacacia</i>
Fir	: <i>Abies</i> sp
Golden false acacia	: <i>Robinia pseudoacacia frisia</i>
Holly	: <i>Ilex aquifolium</i>
Horse chestnut	: <i>Aesculus hippocastanum</i>
Leyland cypress	: <i>X Cuprocyparis leylandii</i>
Lime	: <i>Tilia</i> sp
London plane	: <i>Platanus x hispanica</i>
Maple	: <i>Acer</i> sp
Norway maple	: <i>Acer platanoides</i>
Oak	: <i>Quercus robur</i>
Poplar	: <i>Populus</i> sp
Privet	: <i>Ligustrum vulgare</i>
Red oak	: <i>Quercus rubra</i>
Sweetgum	: <i>Liquidambar styraciflua</i>
Sycamore	: <i>Acer pseudoplatanus</i>
Tree of Heaven	: <i>Ailanthus altissima</i>
Turkey oak	: <i>Quercus cerris</i>
Yew	: <i>Taxus baccata</i>

- **BS 5837 (2012) compliance:** All data has been collected based on the recommendations set out in subsection 4.4 of BS 5837.
- **Tree inspections and site limitations:** Each tree was subjected to a quick visual check level of inspection. Where there is restricted access to the base of a tree, its attributes are assessed from the nearest point of access. Climbing inspections are not carried out during this level of inspection and, if heavy ivy is present, tree condition is assessed from what can be seen from the ground. A separate note is recorded if further investigation may be required to clarify its status.
- **Crown spreads:** Crown spread dimensions are not listed in the tree schedule because they are illustrated on the land survey base to all the plans in this document. Where crown spreads of significant trees on site are found to deviate from those shown on the provided land survey, we have noted it in the text of the report and annotated it on our plans.
- **Dimensions:** All dimensions are estimated unless annotated with a '*'.

Appendix 2: Tree schedule and explanatory notes

- **Species:** Species identification is based on visual observations. Where there is some doubt over tree identity, sp is noted after the genus name to indicate that the species cannot be reliably identified at the time of the survey. Where there is more than one species in a group, only the most frequent are noted and not all the species present may be listed.
- **Height:** Height is estimated to provide a broad indication of the size of the tree.
- **Trunk diameter:** Trunk diameter is estimated or measured and recorded in 2.5cm increments as advised in BS 5837 Table D1. It is measured with a diameter tape unless access is restricted, direct measurement is not possible because of ivy on the trunk or the tree is assessed as poor quality. The point of measurement and the adjustments for stem variations are as advised in Figure C1 of BS 5837.
- **Maturity:** In planning context, maturity provides a simplistic indication of a tree's ability to cope with change and its potential for further growth. For the purposes of this report, young indicates a potential to significantly increase in size and a high ability to cope with change, maturing indicates some potential to increase in size and a medium ability to cope with change, and mature indicates little potential to increase in size and limited ability to cope with change.
- **Low branches:** Any low branches that would not be feasible for removal during normal management and should be considered as a design constraint are noted here and explained in the notes.
- **Category:** Our assessment automatically considered tree physiological/structural condition (BS 5837, 4.4.2.5h), and so these are not listed separately in the schedule. Additionally, the category accounts for the remaining contribution (BS 5837, 4.4.2.5i) as greater than 40 years for A trees, greater than 20 years for B trees, at least 10 years for C trees and less than 10 years for U trees, so this is also not listed separately in the schedule. Category A, B and C trees are automatically listed as sub-category 1 unless otherwise stated.
- **Notes:** Only relevant features relating to physiological or structural condition and low branches that may help clarify the categorisation are recorded. If there are no notes, then the presumption should be that no relevant features were observed.
- **Tree works:** The recommended tree works are based on the quick visual check level of inspection and only intended to address significant hazards identified during that inspection.
- **Future tree safety inspections:** Due to the time that may elapse between the original survey and the start of development, all trees should be re-inspected as part of the standard risk management process before any works start on site. Our assessment of the trees was carried out on the basis that a re-inspection would be carried out within a year of the assessment visit and our advice on tree condition must be reviewed annually from the date of that visit.



Field House
Fordingbridge Business Park
Ashford Road
Fordingbridge
Hampshire
SP6 1BY

01425 651470
info@barrelltreecare.co.uk
www.barrelltreecare.co.uk